



Jim Davis Restoration

1420 N 25th St
Terre Haute, IN 47803
812-234-5895
jimdavis@joink.com

DIANA_ENYEART-1

Main Level

Kitchen

Height: 8'

DESCRIPTION

QTY

1. Mask per square foot for drywall work	262.73 SF
2. R&R 5/8" drywall - hung, taped, ready for texture	32.00 SF
3. R&R Batt insulation - 10" - R30 - paper / foil faced	32.00 SF
4. Texture drywall - smooth / skim coat	58.56 SF
5. Texture drywall - light hand texture	90.56 SF
6. Paint the ceiling - one coat	90.56 SF
7. R&R Fluorescent light fixture - Premium grade Quality: 4 tube, 48" long solid hardwood frame with acrylic drop-in diffuser. Water migrated into the light fixture	1.00 EA
8. R&R Recessed light fixture	1.00 EA
9. Heat/AC register - Mechanically attached - Detach & reset	1.00 EA
10. Final cleaning - construction - Residential	54.22 SF
11. Contents - move out then reset - Small room	1.00 EA

Entry

Height: 8'

DESCRIPTION

QTY

12. Mask and cover light fixture	1.00 EA
13. Mask per square foot for drywall work	183.89 SF
14. Texture drywall - smooth / skim coat	39.00 SF
15. Texture drywall - light hand texture	39.00 SF
16. Paint the ceiling - one coat	39.00 SF
17. Final cleaning - construction - Residential	39.00 SF
18. Contents - move out then reset - Small room	1.00 EA

Living Rom

Height: 8'

DESCRIPTION

QTY

19. Mask per square foot for drywall work	1,027.24 SF
20. Mask and cover light fixture	2.00 EA
21. Texture drywall - smooth / skim coat	367.73 SF
22. Texture drywall - light hand texture	367.73 SF
23. Paint the ceiling - one coat	367.73 SF
24. Heat/AC register - Mechanically attached - Detach & reset	2.00 EA



Jim Davis Restoration

1420 N 25th St
 Terre Haute, IN 47803
 812-234-5895
 jimdavis@joink.com

CONTINUED - Living Rom

DESCRIPTION	QTY
25. Contents - move out then reset - Extra large room	1.00 EA
* 26. Clean and deodorize carpet	367.73 SF
27. Final cleaning - construction - Residential	367.73 SF

Debris Removal

DESCRIPTION	QTY
28. Haul debris - per pickup truck load - including dump fees	0.50 EA

Contained Area

DESCRIPTION	QTY	Height: 8'
Contained Area		Height: 8'
Subroom: Living Rom (2)		Height: 8'
Subroom: Entry (1)		Height: 8'
29. Containment Barrier/Airlock/Decon. Chamber	220.00 SF	
30. Add for personal protective equipment (hazardous cleanup)	6.00 EA	
31. Respirator cartridge - HEPA only (per pair)	2.00 EA	
32. Sand exposed framing - Floor	32.00 SF	
33. Clean more than the walls and ceiling	1,132.77 SF	
34. HEPA Vacuuming - Light - (PER SF)	1,132.77 SF	
35. Hazardous Waste/Mold Cleaning Technician - per hour 5 step cabinets, content inside containment	4.00 HR	
36. Negative air fan/Air scrubber (24 hr period) - No monit.	2.00 DA	

Labor Minimums Applied

DESCRIPTION	QTY
37. Electrical labor minimum	1.00 EA

Grand Total

\$5,227.71